C.R.S. IX—51

Previous references
mc 5-1926 1-2
5-19 " 6-27

1929 ( mc

Revenue

File No 42-22

Serial Nos 426

Later references

# GENERAL AND REVENUE SECRETARIAT.

Serial Nos

Part B for feb 23

SUBJECT

Estimate for Rs 3615/- for erecting a Centrifugal pump in the pumping Station at Harihar

h To, The D C Chitradurg
The Comptroller
The Chief Engineer
No C 5903/C 1922 23
Sanctions the estimate

48
1-3 23

Printed on the Multigraph

From

R. Nanaswami Rao Esquire,
Deputy Commissioner,
Chitaldrug District.

To

T.E.Jayarama Iyer Esq , B.A.,B.L.,
Secretary to Government,
Revenue Department,
B a n g a l o r e.

Dated 11th January 1923.

Despatched

Received

General No C/117 of 22-23
No.

Enclosure No

In forwarding herewith copies of letter No.59 dated 17-11-22 and 89 dated 6-1-1923, from the President, Town Municipal Council, Davangere, submitting for sanction of Government the modified estimate for Rs 3615/- for erecting a centrifugal pump in the pumping station at Harihar for washing the Filter I have the honor to state that the original estimate for Rs 4800/- sanctioned by the Government in 1919 in Water Supply Department was not worked out and the amount is stated to have been refunded by the Water Supply Department while handing over the management of Water Works to the Municipal Council.

The amount required for the work is reported to be met out of the Closing Balance (vide copy of the Resolution enclosed). As the necessity for submitting the modified estimate is clearly explained in the report accompanying the

the estimate which is also enclosed herein, I request that the sanction of Government may kindly be obtained to the same.

Both the original and the modified estimate together with comparative statement and a plan are also forwarded herewith.

I have the honor to be,

S I R,

Your most obedient servant

Deputy Commissioner,
Chitaldrug District.

4

G R S VI G 3-1]

ale

SUBJECT

Diary No of letter replied to 3442 L

Section Irl

File No 42-22

Serial No 6

General and Revenue Secretariat

( L S Q )

, the 192

*Proceedings of the Government of His Highness the Maharaja of Mysore*

Date of issue 19-2-'23

Signed by

I/c The Jumping Station at Hunsur

*Read—*

1 G O No R 1220-21 Irl 5-19-2 & the 22nd Irl 1917 Sanctioning an estimate amounting to Rs 4067 for installing a Centrifugal pump for working the Sluices of the Drainage Water works

2 G O No R 55-62 3 Irl 5-19-7 & the 12th Nov 1919 Sanctioning a Supplemental estimate for Rs 732 being Establishment and Tools and Plant Charges in Connection with the Estimate Sanctioned in the above Order

~~Order Thereon No~~

3 Letter No C 117 Irl 22 23 & the 4th January 1923 from the Dy Comr Hassan District, Submitting for Sanction a Modified Estimate in lieu of the two estimates above Sanctioned in the G O's

for Rs 3,615/-

May this be

i Printed ?

ii treated as a standing order ?

iii published in the Gazette, English Part ?

iv translated ?

v placed at the disposal of the press ?

vi published in the Gazette Kannada Part ?

over

Order No L 5903-58 1912/23

Exec. Engr. Ramanathapuram Div

The models of Estimate
No. PB 3615/- is launched.
The Cost ½ being met from the
Closing balance in favour of
the Sivaganga Town Fund

CE 30.1.23
Orders to file
Rec'd Sept

Asst.
27.1.1923

To

The Sub Collr Ruthalapuram Dist
with the models of Estimate & plan & the file
" Comptr
" Exe Engr for Irrigation

Last of enclosures

Copied by

Examined by

WD 1333—GPB—1,000,000—21 12-2

M A M 70] *(Rule 250)*

# COMPARATIVE STATEMENT FOR REVISED ESTIMATE

W D A 0943—GEPM—9 11 17

| Description of work | Original Estimate | | | | Revised Estimate | | | | More | Less | Explanation of difference |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Quantity | Rate | Per | Amount | Quantity | Rate | Per | Amount | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| 1 Centrifugal Pump | 1- | 1500 | No | 1500 | 1 | 800 | No | 800 | — | 700 | owing to favourable market rate |
| 2 Foot Valve | 1 | 200 | No | 200 | 1 | 100 | No | 100 | — | 100 | — do — |
| 3 Suction pipe | 5' | 20 | Cubt | 100 | 12 | 16 | Cubt | 192 | 92 | — | The length is more as the pump is to be located in a room outside the building favourable market rate |
| 4 Delivery pipe | 18 | 20 | " | 360 | 15 | 16 | " | 240 | | 120 | |
| 5 Stop valves | 2 | 200 | No | 400 | 2 | 150 | No | 300 | — | 100 | — do — |
| 6 Bends | 20 | 28 | Cubt | 560 | 6½ | 18 | Cubt | 117 | — | 443 | The line to Shanghat, V so many bends are now required |
| 7 Tee 6"x8" | 1 | 75 | No | 75 | — | — | — | — | — | 75 | do do not required |
| 8 Belt pulleys | 1 | 100 | No | 100 | | | | | | | due to shifting of wall brackets to do as to take drive from the big size shaft |
| 9 Belt 5" wide | 40 | 8 | Rft | 180 | | 2½ | — | 400 | 125 | — | |
| 10 Iron door | | 2½ | | 25 | | | | | | | |
| 11 Lapa pipes 8"x6" 6"x5" | — | — | — | — | — | — | 2½ | 45 | 45 | — | To reduce friction the size of both suction and delivery are made bigger than the inlet mouth of pump |
| | | | Total | 3470 | | | | 2194 | 267 | 1843 | |

Station

Dated 191

*President*

*Office in charge*

M A M 70] (*Rule 250*)

# COMPARATIVE STATEMENT FOR REVISED ESTIMATE

W D A 0943—GBPM—9-11 17

| Description of work | Original Estimate | | | | Revised Estimate | | | | More | Less | Explanation of difference |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Quantity | Rate | Per | Amount | Quantity | Rate | Per | Amount | | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
| B/F | | | | 3470 - - | | | | 2194 - - | 287 - - | 1863 - - | |
| 1 Erection of pump | | Ld | | 150 - - | | - - | | 178 - - | 28 - - | - - - - | a heavy foundation is necessary since the pump has to go at a high speed |
| 2 Casting from Stn | | - - - | do | 30 - | | | | - - - | - - - | - - - | Stn = Station: No cost of pump |
| 3 Excavating pipe line | 2 | - 6 - | C/S | 1 - - | | | | | | | |
| 4 Plastering with mortar | 122 | 3 - | Sq | 4 - - | | | | | | | Since most of the line round the new room remaining is plain concreting with slabs is not necessary |
| 5 Covering with slabs | 70 | - 4 - | Yd | 15 - - | | Ls | | 140 - - | - - - | 73 - - | |
| 6 Laying pipes etc | | Ls | | 150 | | | | | | | |
| 7 Washing Sump | | | do | 30 - | | - - | | - - - | - - - | 30 - - | The suction is not from the Sump hence leaving |
| 8 Conlingen cies | | - - - | - | 194 - - | | - - | | 120 - - | - - - | 74 - - | Casting to Earthwork Estimate - |
| 9 Establishment tools & plant charges | - | - - - | - | 733 - - | - | - - | - | - - - | - - - | 733 - - | The work is to be executed under the supervision of the municipality |
| 10 Extending Engine Room | - | - - - | - | - - - - | - | - - | - | 1023 - - | 1023 - - | - - - - | A new room is provided as per Superintending Engineers instructions |
| | | Total | | 4900 - - | | | | 3615 - - | 1330 - - | 2523 - - | |

Station

Dated 191

2/ — 4/1/23
President

net 1185/- less

L. Hutchadas
Officer in charge
Asst Engineer